ELECON REVS





Municipal Pool Selects
DuraQuartz Lightweight &
ENESEAL HR For Overhead
Concrete Repairs

Location: Municipal pool located in eastern U.S.

Problem: After years of leaking windows & skylights, the overhead concrete ceiling of this indoor pool building began to crack and spall. The potential for concrete chunks to fall into the pool while it was in use was a serious safety concern of the pool maintenance team.

Solution: The pool was first protected with tarps. Under the tarps were pieces of foam to prevent the tarps from sinking during the concrete preparation.

The concrete was prepared by manually chipping away any loose concrete near the cracks. The prepared areas were then primed and DuraQuartz LW was used to make the repairs. After the repairs were made two coats of ENESEAL HR were then applied.









