Commuter Rail System Saves Time, Money & Commuter Aggravation with ENECRETE & CHEMCLAD



Client: Northeastern U.S. commuter rail system.

Problem: Failed existing platform coating, on important NYC transfer station servicing thousands of commuters daily, was creating trip, slip and fall hazards.

Solution: Removal of failed coating followed by DuraFill with a locally sourced aggregate was used to repair damaged concrete areas and seal the entire platform. Two coats of CHEMCLAD SC with an aggregate to provide slip resistance were then applied.

Savings: This turn key job only took seven days compared to one year of planning, review and approvals for complete replacement.









CH-085





6 Platinum Court • Medford, NY 11763 Toll Free: 888-4-ENECON® (888-436-3266) • Phone: 516-349-0022 • Fax: 516-349-5522 www.enecon.com • info@enecon.com

Copyright ©2017 by ENECON® Corporation.

